



## VERIZON BUILDING, ROANOKE , VA

ARCHITECT: Baskerville Architects  
GENERAL CONTRACTOR: Tishman Construction Corporation of DC  
PRODUCT INSTALLED: Insulated Metal Wall Panels, Custom Steel Substrate  
SUPPLIERS: Kingspan Benchmark Insulated Wall Panels

There was over 50,000 sq. ft. of insulated panel product used for this project requiring installation to occur in sequence, with no possibility of replacing panels individually. ADG designed a way to remove and replace the panels individually as needed, in order to accommodate installation of the hydro mobile system which was used for installation of the panel system.

### KEY ELEMENTS OF PROJECT

This building was originally clad in large slabs of marble. Over time the marble began falling from the building into the streets below. The checkered pattern of the various colored panels gives the building a modern art look.

### SPECIAL EQUIPMENT REQUIRED TO INSTALL

To install the 23' wide, 2" thick insulated panels, ADG erected a vertically moving, hydro-mobile scaffold system. This allowed for large amounts of panel square footage to be set daily.

[Please go to our website to view TIME LAPSE photography of this project.](#)

CURTAINWALL

ARCHITECTURAL GLASS

PANELS

STOREFRONT

WINDOWS & DOORS



350 Apperson Drive | Salem, VA 24153  
phone: 540-387-1612 | toll free: 877-ADG-1612  
fax: 540-387-1679  
[www.americandoorandglass.com](http://www.americandoorandglass.com)